Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Narasimaiah	
				In Figures	In Words
7	14.40	Providing and constructing precast concrete solid blocks with compressive stength not less than 35 Kg/sqm with cement mortar 1:4 masonry (quoin,jamb,closer blocks)with solid concrete blocks of size 40x20x20cms conforming to I.S 2185/1965 in superstrucure including cost of materials, labour charges,scaffolding curing complete as per specifications	Sqm	671.00	Rupees Six Hundred Seventy One Only
8	1.80	Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not excedding 15cms. Thick well compacted in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specification	Cum	4897.00	Rupees Four Thousand Eight Hundred Ninety Seven Only
9	15.00	Providing and fixing MS square Jally 9"x9" (grating) for shoulder drains fixing with cement mortar including cost of all materials, lanour curing complete as per specifications and as directed by the Engineer in charge.	No.	129.00	Rupees One Hundred Twenty Nine Only
10	120.00	Earthwork in excavation (in deposited soil) and filling sides of foundation upto plinth in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with all lead and lift including cost of all labour complete as per specifications.	cum	184.00	Rupees One Hundred Eighty Four Only
11	990.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 10cms thick	Sqm	476.00	Rupees Four Hundred Seventy Six Only
12	990.00	Providing two line dressing to granite stone slab/granite stone masonry as per specification	Sqm	658.00	Rupees Six Hundred Fifty Eight Only
13	3900.00	Providing machine cutting granite stone slab edges as per direction of engineer in charge (Approved Rate)	Rmt	58.00	Rupees Fifty Eight Only
14	666.67	Providing and fixing pre cast solid cement concrete kerb stones made out of C C 1:2:4 with top and bottom width 114 and 165mm resepctively, 400mm high and 450 mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing including cost of all materials labour hire charges of machinery loading, un loading lead and lift trasportation etc. complete	No	239.20	Rupees Two Hundred Thirty Nine and Twenty Paise Only
15	135.00	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plasterd concrete surfaces with materials labour complete as per specifications. Specification No KRBS 800.3 MORT & H Specification No. 800	Sqm	47.00	Rupees Forty Seven Only

ಸಹಾಯಕ ಇಂಜಿನಿಯರ್
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ,
ಬೃ.ಬೆ.ಮ.ಪಾ. ಯಲಹಂಕ ವಲಯ
ಸಹಕಾರನಗರ, ಬೆಂಗಳೂರು-೯೨.

N. ನಿರಂಜನ ಮೂರ್ತಿ

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Narasimaiah	
				In Figures	In Words
16	117.00	Haulage of materials by tipper including cost of loading, unloading and stacking Complete as per specifications. MORTH chapete 1 case-1: Surface Road	cum	119.00	Rupees One Hundred Nineteen Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

BRUHAT BANGALORE MAHANAGARA PALIKE

Item No. 05

APPROVED SCHEDULE - B

Tender Notification No: BBMP/ EE /Btp/Ten/13/2011-12 Dated: 10-02-2012

Name of Work : Imrovements to Drains and Footpath around devinagar near RMV Apartment in Kodigehalli in ward No. 8 Kodigehalli sub division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of Narasimaiah	
				In Figures	In Words
1	27.00	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	Cum	113.00	Rupees One Hundred Thirteen Only
2	90.00	Earthwork excavation by manual means in Ordinary Soil involving an average horizontal throw upto 2 meters and an average lift upti 0.5 m excavated surface levelled and sides neatly after breaking of clods complete as per specifications with all leads and labour and conveying the earth to 15 km loading and unloading charges	Cum	59.00	Rupees Fifty Nine Only
3	31.05	Providing and constructing granite/trap/baslt size stone masonry in foundation with cement mortar 1:6 stone hammerd dressed in courses not less than 20cms high.bond stones at two m apartt course including cost of materials labour curing complete as per specification	Cum	2726.00	Rupees Two Thousand Seven Hundred Twenty Six Only
4	60.00	Providing and constructing non-load bearing wall with cement concrete solid blocks with compressive strength not less than 35 Kg/sqm with cement mortar 1:4 (jamb,closer blocks)with blocks of size 40x10x20 cms (Lxbxh) conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications	Sqm	481.00	Rupees Four Hundred Eighty One Only
5	120.00	Providing flush pointing to coursed stone masonry with cement mortar 1:3, 20mm deep after raking joints to depth of 20mm, nicely lining, including cost of materials, labour curing complete as per specifications	Sqm	71.00	Rupees Seventy One Only
6	19.50	Providing and laying in position plain cement concrete of nominal mix 1:2:4 using 20mm and down size graded granite metal, machine mixed, concrete laid in layers not excedding 15cms. Thick well compacted in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specification.	Cum	4897.00	Rupees Four Thousand Eight Hundred Ninety Seven Only

ಕಾರ್ಯಪಾಲಕ ಇಂಜಿನಿಯರ್
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ,
ಬೃ.ಬೆ.ಮ.ಪಾ. ಯಲಹಂಕ ವಲಯ
ಸಹಕಾರನಗರ, ಬಂಗಳೂರು-92.